

# **FEXI**BILITY AS DESIGN CONCEPT

Introduction to the new generation flexible, modular facilities by KeyPlants®





# 80% of all conventional construction projects are delayed more than 4 months

Source: Industry Best Practise Construction Industry Institute (CII) USA www.constuction-institute.org

### **Problems: Conventional Execution**



- Inefficient utilization of the facility area lay-out increase construction/operation cost (HVAC etc)
- Control of many suppliers and sub-contractors is time consuming
- Escalation (change orders 10 15% of conventional project cost)
- A typical cost escalation of a project is + 15 50%, schedule slip additional 3 – 6 months
- Quality (workmanship varies with installations companies and market)





#### **Benefits from Modular construction**

#### -Predictability

(comparison on one project of Stick-built versus modular: for cost, schedule, quality, and productivity)

Compliance to plan:	<u>Cost</u>	<u>Schedule (1)</u>	Quality
Stick-built (2)	+15 to 50%	+3 to 6 months	Site dependent
Modular	+5 to 10%	+1 to 2 months	Predictable

Note: (1) Does not account for the schedule gains(6 to 10months) with respect to the Stick-built delivery. (2)Data based on large Biotech Facility; Site conditions productivity, rework... 1 Hr in a shop requires 4 hrs in the field



### Outdoor or ...






# Indoor modules



#### Four weeks on site!


### **Project Execution Model**





## **Modular Project Execution**





# Modular Assembly at Site




The Genentech Example




# Enhanced financial performance





Enhanced Cash Flow
 Enhances cash flow due to shorter
 implementation schedule



This significantly raises the **NET PRESENT VALUE** 

Higher Project Net Present Value
 Increases net present value of the investment in real terms

#### © KeyPlants All rights reserved

# **Risk Mitigation**

- SD modular design, process design and execution experience
- Faster and predictable execution
- Fixed price offering after Basic
  Engineering
- Pre-IQ and pre-testing
- Movable asset

tforms

- Off site construction in ISO 9001 certified factory
- Standardized, pre-engineered






### The Flexible MBS<sup>™</sup> Platform



and clean utility generation.

Optimized flexibility by allowing easy re-configuration



Scalable capacity, 500, 1 000 to X \* 2 000 L SUB:s

# The Flexible MAS<sup>™</sup> Platform



Complete building with fixed installations, process equipment and clean utility generation.



RABS Container: 2-2 Capacity: 100/min

2- 20 ml vials 200/min 10 ml vials

Isolator

All these platforms can be modified to fit the required cap


0,5 – 10 ml 200/min 1 ml

# Flexibility – Single use or SS



ndent of any vendor or process – gives the client flexibility to stay irrent vendor or possibilities to negotiate best price 100 % stainless steel 100 % single-use design with maximized use of single-use equipment  $\longrightarrow$  100 % hcare illipore sher Scientificrs thcare Life Sciences

# Flexibility - Level of Segregation



**Key**Plants<sup>®</sup>


# Flexibility – Full Integration



# A fully integrated facility through easy expansion and connections according to needs – a hybrid

- Add on for MAS (Modular Aseptic Solutions™)
- Add on for Utilities
- Connection to Conventionally Contructed Warehouse
- Connection to Conventional Laboratory
- Connection to Conventional Administration





# Flexibility- Relocation of Facility





oly at first site



2. New site in preparation during disassembly



3. Reassembly at new site





gain?, same site

4. Facility in operation at new site

# **Flexible Scope**



candard covers the manufacturing process from seed ultivation, harvest, purification to filled bulk in cold ge (optional MAS aseptic filling)




ng Management System and the support functions ng and sterilization, weigh and dispense, in process ol and disposable waste












# Accelerated Schedule, Overlapping KeyPlants





# **CON**CEPTUAL LAYOUTS

Microbial Vaccines MV
 Therapeutic Proteins TP
 Live Viral Vaccines LVV, BSL3 containment
 CMO Multipurpose



# **1. MICROBIAL VACCINE, M**

Conceptual Layout


# **Configurations MV**



ng minor configurations to the pre-engineered flexible latform Modular Bio Solutions™ have been made:



SIP added since there are stainless steel process oment





storage added



# 2. THERAPEUTIC PROTEINS

Conceptual Layout

# **Configurations TP**



- ng minor configurations of the pre-engineered design n Modular Bio Solutions™ have been made:

ased Cultivation and Initial purification area

ased Media and Buffer prep/hold area

e addition of CIP/SIP, Column Packing and Cold age as for the process MV



# **3.** LIVE VIRAL VACCINE, LVV

Conceptual Layout

# **Configurations LVV**



Modular Bio Solutions™ have been made:



ased the level of segregation to meet the rements of BSL3 and handling of Live Virus by ig airlocks in to the live area.

rea also includes a Virus seed lab in Grade C

disposeable



# 4. CMO MULTIPURPOSE

Conceptual Layout

# **Configurations MP**



- ng configurations of the pre-engineered design n Modular Bio Solutions™ have been made:
- to limited area on site a CMO requested a two storey guration based on the MBS platform



egregation between cultivation and initial ication

disposables (as in the original design)



ugh the floor segregation to final purification



er/Media carts by elevator to Buffer/Media hold.

# Why Modular Platforms?

- ROI (WORTH) WHAT WE GIVE (INVESTMENT) COSTS BENEFITS WHAT WE GET (RETURN)
- Schedule within one year shorter time to market
- Improved flexibility to produce several vaccines
- Enhanced value with integrated design and construction capability
- Subject Matter Experts in Aseptic and Biotech Processing
- Higher quality with off-site fabrication workshop ISO 9001 and OHSAS 18001 certified, with only specilized labour for all disciplines
- 3D modeling for efficient client and discipline coordination
- Standard busice offer fixed price (ex works) after completed and accepted P
- Standarc succepts for shorter implementation at reduced cost. Cost of operations reduced through savings in labor, QA cost, validation, tenance, utility and energy

# **KeyPlants Globally**



#### Global capabilities in Life Sciences and Process Manufacturing Industries



Part of Telstar/Azbil Group with > 2 Billion Euro in turnover and 9 000 employees whereof + 900 pharma specialists

### **Our Services**



#### 🧇 Ser

- Conceptual Design
- Basic Engineering
- Detailed Engineering and Execution
- EPCM contracts
- Turn-Key Delivery
- Consultancy (Feasibility studies etc.)

#### Project Types

- Green field/Brown field
- Upgrades, Expansions and Renovations

#### Standard Facilities

- MAS (Modular Aseptic Solutions)
- MBS (Modular Bio Solutions)

#### Complete Range of Modular Solution

- Building Modules
- Indoor Modules
- Process Modules/Super Skids





# Acknowledgements







### KeyPlants' & Big Pharma



